
Designing a BSL3 Facility

Sandia National Laboratories
Laboratory Biosecurity and Biosafety
for BSL3 Laboratories
India
Jan 2007

www.biosecurity.sandia.gov

Biocontainment

- **Biocontainment is the control of biohazards through**
 - **Practices & procedures, including administrative controls**
 - Good lab practices
 - Written SOPs for research activities, specialized equipment, etc
 - Required training
 - Access requirements
 - **Primary barriers (safety equipment)**
 - Biosafety cabinets (BSCs)
 - Lab equipment (pipetting devices, waste containers, safety centrifuge cups)
 - Personal protective equipment
 - **Secondary barriers (engineering & architectural controls)**
 - Building & room construction – the floor plan
 - HVAC issues – directional airflow, filtration
 - Waste treatment


Biosafety Levels

- **Biosafety Levels**

- Four biosafety levels provide increasing degrees of protection
- What's the right balance of practices & procedures, primary barriers and secondary barriers?

- **Applications:**


- Labs (BSL-1, 2, 3, 4)
- (Small) Animal Containment (ABSL-1, 2, 3, 4)
- Large Animal Containment (“BSL-3 AG”)
- Plant Containment (BSL-1P, 2P, 3P, 4P)



Guidance and Regulations

- **Performance-based vs. prescriptive**
 - A performance approach generally defines what result is intended, leaving how to achieve the result up to the user.
 - Prescriptive approaches outline specific requirements that must be done.
- **WHO Laboratory Biosafety Manual – 3rd edition**

- See CD for WHO LBM




Planning: Facility Vision

- **Where should the facility be located?**
- **What should the facility do?**
- **How should it be staffed?**
- **How will it be supported?**
- **What is the path to achieving adequate training and resources?**
- **How should it be linked to existing or planned public/agricultural health authorities in country and internationally?**
- **How does the facility fit into the country's goals for public/agricultural health and science?**
- **What is the expected public reaction?**
- **What support (financial, collaborative, other) will be needed for construction, staffing, training? From where?**
- **How does the facility see itself contributing to the global scientific community?**
- **What is the long-term plan to ensure sustainability?**

Planning: Risk Assessment is Critical

- Identify biological agents that will be used
- Perform risk assessment
 - Include an evaluation of settings
 - Labs
 - Animal housing
 - Patient care
 - Autopsy/Necropsy
 - Other?
 - And activities:
 - At the macro scale: research, diagnostics, health care, industry, other?
 - At the micro scale: routine manipulations, producing large volumes, aerosolization, animal testing, other?
- Determine biosafety level
 - What degree of biocontainment is necessary to mitigate the risk?



Engineering Controls

- **The first and best strategy in biocontainment is to control the hazard at the source**
 - **If feasible, design the facility, equipment, or process to remove the hazard or substitute something that is not hazardous**
 - **If removal is not feasible, enclose the hazard to prevent exposure in normal operations**
 - **Where complete enclosure is not feasible, establish barriers and/or localized controls to reduce exposure to the hazard in normal operations**
- **Apply before work practices and personal protective equipment are used**
- **Engineering and other types of controls (including PPE) are NOT mutually exclusive**
- **Employers may need to use multiple types of controls to prevent employee exposure**
- **Degree to which engineering controls are required depends on the applicable regulatory framework (incl. guidelines) and a site-specific risk assessment**



Containment Barriers

- **Barriers provide protection by:**
 - Physical separation
 - Directional airflow (differential pressure)
 - Practices and procedures
 - Decontamination
 - Filtration

- **Barriers are penetrated by:**
 - Personnel
 - Fluids
 - Air, gases, water, drainage...
 - Materials
 - Products




Biosafety Level 1: Facility Design

- **Requirements:**
 - Laboratories have doors
 - Sink for hand washing
 - Work surfaces easily cleaned
 - Bench tops are impervious to water
 - Sturdy furniture
 - Windows fitted with flyscreens
- **Other design and construction issues:**
 - Location – not separated
 - Structure – normal construction
 - Ventilation – no special requirements

Easily cleaned and decontaminated



Biosafety Level 1: Facility Design




Biosafety Level 2: Facility Design

- **Requirements:**
 - **Laboratories have lockable doors**
 - **Sink for hand washing**
 - **Work surfaces easily cleaned**
 - **Bench tops are impervious to water**
 - **Sturdy furniture**
 - **Biological safety cabinets installed as needed**
 - **Adequate illumination**
 - **Eyewash readily available**
 - **Windows fitted with flyscreens**
 - **Location - separated from public areas**
 - **Ventilation – directional**
 - **Air flows into lab without re-circulation to non-lab areas**



Restricted access
when work in progress

Biosafety Level 2: Facility Design




Biosafety Level 3: Facility Design

- **Requirements:**
 - **BSL-1 and 2 Facilities PLUS**
 - Enclosures for aerosol generating equipment
 - Room penetrations sealed
 - Walls, floors and ceilings are water resistant for easy cleaning
 - BSC class II or III to manipulate infectious material
 - Separate building or isolated zone within a building
 - Directional inward airflow
 - Single-pass air
 - Double door entry
 - BSCs mandatory
- **Additional requirements depending on work and agents:**
 - HEPA filtration of the exhaust
 - Effluent decontamination
 - Personnel showers




Follow the guidelines, regulations, and site-specific risk assessment for your unique situation!



Biosafety Level 3: Facility Design




Options for Double Door Entry




ROOM AS ACCESS ZONE



CORRIDOR AS ACCESS ZONE



SUITE CONCEPT



LAB AS ACCESS ZONE



CORRIDOR



ACCESS ZONE



BSL3



ENTRY DOOR 1




ENTRY DOOR 2




Directional Airflow

- **When Do You Need Directional Airflow?**
- **Airflow Offset Control**
 - Relies on airflow through doors at all times
 - “Leaky Box”
 - Provides “Zone Control” of hazards and odors



Airflow Offset Control



“Leaky” Level 3

Heating Ventilation and Air Conditioning Issues



- Pressure monitoring devices at entry
- Smoke test
- HVAC controlled to prevent sustained positive pressurization
- Interlock exhaust/supply
- Alarms for HVAC failure (inside and outside the facility)
- Exhaust air HEPA filtered (sometimes necessary)
- Sealed ductwork
- Backflow prevention on supply air (Damper, HEPA)

The Birth of a New Laboratory

- **1. Planning**
 - Define project / team
 - Budget
 - Schedule
 - Owner requirements
 - Goals
 - Functional requirements
 - Codes, Standards, Guidelines
- **2. Design**
 - Budget
 - Schedule
 - Design stages
 - Construction documents – drawing and specifications
- **3. Construction**
 - Procurement
 - Budget
 - Construction schedule
 - Build
 - Installation and Inspections
 - Startup and testing
 - Training
 - Turnover
- **4. Occupancy**
 - Move in
 - Training
 - Periodic testing
 - Go hot

Commissioning

- **What: A process to ensure that the completed facility meets the needs of the end user:**
 - Safety
 - Security
 - Reliability
- **Why: Necessary because all labs are prototypes**
 - Layout
 - Functional intent
 - Fit and Finish
 - Systems arrangement
 - Cost
- **When: Throughout process – planning, design, construction, occupancy**

Commissioning Responsibilities

Throughout the Development of a New LAB

- **Planning Phase**
 - Establish commissioning team
 - Review owner requirements
 - Scope and budget for commissioning
 - Develop plan for commissioning (who, what, where, how, when)
- **Design Phase**
 - Develop commissioning specifications
 - Process
 - Component verification checklists
 - Systems test forms
 - Integrated systems forms
 - Training
 - Documentation

Commissioning Responsibilities Throughout the Development of a New LAB

- **Construction Phase**
 - Commissioning schedule
 - Complete component verification checklists
 - Develop test procedures
 - Test
 - Oversee resolution of issues
 - Training
- **Occupancy Phase**
 - Warranty review
 - Seasonal testing
 - Oversee resolution of issues
 - Document baseline



Commissioning Test Process

- **Component verification**
 - Verification that component meets design intent and technical requirements
 - **System test**
 - Testing to ensure fully functional system under all operational parameters
 - **Integrated system test**
 - Interdependency of systems and final facility validation
-
- See CD for Websites: Laboratory Commissioning

Summary

- **Risk assessment should determine facility design**
- **Biocontainment can be achieved through a variety of strategies**
 - **Balance of primary barriers, secondary barriers, and procedures and practices**
- **BSL 3 lab builds upon the requirements for BSL 1 and BSL 2 labs**
- **Every lab is unique – need to ensure lab will work as intended**
 - **Commissioning**
- **Designing and building a lab is only the start**
 - **Must plan for maintenance and long-term sustainability**